

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22790-00-00
Spot: SWSWNESE Sec/Twnshp/Rge: 12-15S-21W
1555 feet from S Section Line, 1000 feet from E Section Line
Lease Name: KING Well #: B#1
County: TREGO Total Vertical Depth: 4000 feet

Operator License No.: 6484
Op Name: ANDERSON ENERGY, INC.
Address: 300 W DOUGLAS AVE, STE 410
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	307		200 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/09/2012 12:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Revd. from: BILL Company: SOUTHWIND DRILLING, INC. Phone: (620) 617-0706

Proposed Plugging Method: Ordered 245 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DAVID WANN
Date/Time Plugging Completed: 06/09/2012 3:00 AM

Witness Type: NONE
KCC Agent: DAVID WANN

Actual Plugging Report:

1st plug @3874 w/25 sx
2nd plug @1440 w/25 sx
3rd plug @640 w/100 sx
4th plug @360 w/40 sx
5th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

District: 04

Signed: 
6/15/12 (TECHNICIAN)

RECEIVED
JUN 14 2012
KCC WICHITA
CM

JUN 11 2012