

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Operator: Cities Service Oil & Gas Corp.
Name & Address 800 Sutton Place, 208 East William
Wichita, KS 67202

API NUMBER 15-083-21.155
SW SW SE, SEC. 29, T 23 S, R 24 W/X
330 ^{FS} feet N SE Corner of
2310 ^{FEV} feet W SE Corner of
feet from ~~XXX~~ section line

Lease Name Mollenkamp Well # "A" 1

County Hodgeman

Well Total Depth 4885 158.76 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 599

Abandoned Oil Well Gas Well Input Well SMD Well D&A X

Other well as hereinafter indicated

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address 401 East Douglas, Wichita, KS 67202

Company to plug at: Hour: 4:00 am Day: 28 Month: August Year: 19 84

Plugging proposal received from Mike Malone

(company name) Cities Service (phone) 316-265-5624

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1680' with 50 sx cement

2nd plug at 750' with 70 sx cement

solid bridge
3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by R. Barburton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:00 pm Day: 28 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1680' with 50 sx cement, 2nd plug at 750' with 70
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface
with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton No. 824512
(if additional description necessary, use BACK of this form.)

I ~~did~~ / did not observe this plugging.

9-10-84

3601

8-28

RECEIVED
STATE CORPORATION COMMISSION
SEP 04 1984
9-4-84
CONSERVATION DIVISION
Wichita, Kansas

Signed R. Barburton
(TECHNICIAN)