

6 20 6 135-20041-0000

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Date 7/67

C NW SW, SEC. 4, T 17 S, R 23 W/E

1980 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Harkness Unit Well # A-2

Operator: Murfin Drilling Company

County Ness 144.37

Name & Address 250 N. Water, Suite 300

Well Total Depth 4442 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 85/8 feet 306

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 1:20 p.m. Day: 28 Month: 6 Year: 19 90

Plugging proposal received from John Turner

(company name) Murfin Drilling Company (phone) 913-462-6781

were: 5 1/2" at 4420' Open hole 4420-42' Tubing stub 2662'

1st plug perforate at 1050', pump 80 sx cement,

2nd plug pump 150 sx cement down annulus.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:50 p.m. Day: 28 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug perforated 5 1/2" at 1050', pumped 180 sx cement down

5 1/2", 400 psi maximum pressure, 100 psi shut in, 7-3-90

2nd plug pumped 150 sx cement down backside, 300 psi maximum pressure, 150 psi shut in.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOLCED

(If possible, observe this plugging.)

DATE 7-9-90

Signed Dan Goodner (TECHNICIAN)

INV. NO. 28555

6-28