

135-20170-0000

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Date 9/68

C SW SW, SEC. 4, T 17 S, R 23 W/EX
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6033

Lease Name Harkness Unit Well # A-3

Operator: Murfin Drilling Company
Name & Address 250 N. Water, Suite 300
Wichita, KS 67202

County Ness 144.33

Well Total Depth 4441 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 318

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 10:45 a.m. Day: 28 Month: 6 Year: 19 90

Plugging proposal received from John Turner

(company name) Murfin Drilling Company (phone) 913-462-6781

were: 5 1/2" at 4432' Open hole 4432-41' Tubing stub at 1207'
1st plug perforate at 1050', pump 80 sx cement,
2nd plug squeeze annulus with 150 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 28 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug perforated 5 1/2" at 1050', pumped 80 sx cement to circulate
up backside, shut in backside,

2nd plug pumped 250 sx cement down 5 1/2".
Maximum pressure 350 psi and shut in 200 psi.

7-3-90
JUL 3 1990

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-9-90

Signed Dan Goodson
(TECHNICIAN)

INV. NO. 28549
6-28