

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-20167-00-00
Spot: CNENE Sec/Twnshp/Rge: 8-17S-23W
660 feet from N Section Line, 660 feet from E Section Line
Lease/Unit Name: HORCHEM Well Number: 1
County: NESS Total Vertical Depth: 4464 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 309 WITH 200 SX CMT
Production: Size 5.5 feet: 4448 100 SX CMT/50 GAL. LAT
Liner: Size feet: 8/45.08

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/16/2001 10:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: BOTTOM PLUG PUMP 25 SX CMT THROUGH TUBING. PERFORATE AT 900'. PUMP 80 SX CMT OVER CASING VOLUME USE 150 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/16/2001 2:15 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PERFS AT 4350-56'. OPEN HOLE 4448-65'. RAN TUBING IN HOLE TO 4422'. PUMPED 30 SX CMT WITH 200# HULLS. PULLED TUBING UP TO 923' CIRCULATED CMT TO SURFACE WITH 155 SX CMT. WELL WENT ON VACUUM. PULLED TUBING UP TO 403' PUMPED 125 SX CMT. HAD NO CIRCULATION BUT HAD GOOD BLOW. PULLED TUBING OUT OF HOLE. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 90 SX CMT. MAXIMUM PRESSURE 400#. SHUT IN @ 250#. TOPPED OFF 5 1/2" WITH 40 SX CMT. HOLE STAYED LOADED.

RECEIVED

AUG 24 2001
8-24-01
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

AUG 20 2001

8-27-01
2002060282 MP

