

To: 1 090105  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-23,583-0000 29R  
SE NE SE, SEC. 8, T 17 S, R 23 W/EX  
1650 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5538  
Operator: Tomkat, Ltd.  
Name & Address: P.O. Box 20403  
Wichita, KS 67208

Lease Name Harkness Well # 1  
County Ness 147.06  
Well Total Depth 4525 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 211

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A  X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Blue Goose Drilling Company, Inc. License Number 5104  
Address P.O. Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 3 Month: 8 Year: 19 91

Plugging proposal received from Martin Miller  
(company name) Blue Goose Drilling Company, Inc. (phone) 316-792-5633

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1760-1809'

- 1st plug at 1800' with 50 sx cement, 2nd plug at 1000' with 80 sx cement,
- 3rd plug at 500' with 50 sx cement, 4th plug at 240' with 50 sx cement,
- 5th plug at 40' with 10 sx cement,
- 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X

Operations Completed: Hour: 3:30 p.m. Day: 3 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 1800' with 50 sx cement,  
2nd plug at 1000' with 80 sx cement,  
3rd plug at 500' with 50 sx cement,  
4th plug at 240' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 07 1991  
8-7-91  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.  
(if additional description is necessary, use BACK of this form.)

**INVOICED**

DATE SEP 06 1991

INV. NO. 32987  
8-3

Signed   
(TECHNICIAN)