

1060147

TO: STATE CORPORATION COMMISSION

2-16

API NUMBER 15-135-23,936-0001
SE SE NE SEC. 17, T 17 S, R 23 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME ALBERS WELL # 1 (OWWO)

TECHNICIAN'S PLUGGING REPORT COUNTY NESS 146.38

OPERATOR LICENSE # 5010 WELL TOTAL DEPTH 4504 FEET

OPERATOR: KNIGHTON OIL COMPANY, INC PRODUCTION CSG: SIZE 5 1/2" @ 4502' WITH 165 SX

NAME AND ADDRESS 221 S BROADWAY, SUITE 710 SURFACE CASING: SIZE 8 5/8" @ 312' WITH SX

WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING AND SALVAGE LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 4:10 PM DAY: 16 MONTH: 02 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2943

WERE: PERFS @ 4338-44

1ST PLUG SANDED TO 4250' WITH 4 SX CEMENT. 2ND PLUG AT 1720' WITH 50 SX CEMENT.

3RD PLUG AT 850' WITH 50 SX CEMENT. 4TH PLUG AT 320' WITH 40 SX CEMENT.

5TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 6:00 PM DAY: 16 MONTH: 02 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SANDED TO 4250' WITH 4 SX CEMENT. 2ND PLUG AT 1720' WITH 50 SX CEMENT.

3RD PLUG AT 850' WITH 50 SX CEMENT. 4TH PLUG AT 320' WITH 40 SX CEMENT.

5TH PLUG AT 40' WITH 10 SX CEMENT.

RECEIVED
KANSAS CORP
3-2-99
12:03

REMARKS: USED 60/40 POZMIX 6% BY ALLIED. Recovered 3320' of 5 1/2 casing.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED

3-10-99

I DID OBSERVE THIS PLUGGING.

DATE

SIGNED

Michael J. Maier
(TECHNICIAN)

FORM CP-2/3

INV. NO. 60693