

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 135-23,936-0006

SE SE NE, SEC. 17, T 17 S, R 23 W/E

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5215

Lease Name Albers Well # 1

Operator: Lee Phillips Oil Company

County Ness

Name & Address 151 Whittier, #1400

Well Total Depth 4504 146.38 feet

Wichita, KS 67207-1045

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 312

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Mallard JV, Inc.

Plugging Contractor License Number 4958

Address P.O. Box 1009, McPherson, KS 67460

Company to plug at: Hour: 2:15 p.m. Day: 3 Month: 6 Year: 19 96

Plugging proposal received from Carol

(company name) Mallard JV, Inc. (phone) 316-241-4640

purpose: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1776' with 50 sx cement, 2nd plug at 888' with 80 sx cement,

3rd plug at 333' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Bill Johnson (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4 p.m. Day: 3 Month: 6 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 1776' with 50 sx cement,

2nd plug at 888' with 80 sx cement,

3rd plug at 333' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.

If additional description is necessary, use back of this form.

(Agent, did not) observe this plugging.

DATE JUN 24 1996

W.V. NO. 45863

Signed [Signature] (TECHNICIAN)

EFFECTIVE DATE: 5-22-96

State of Kansas

135-23,936 .0000

DISTRICT # 1
SGA? Yes No

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date May 25 1996
month day year

Spot SE - SE - NE Sec .17. Twp 17. S, Rg .23. X East West

PERMITOR: License # 5215
Name: Lee Phillips Oil Company
Address: 151 Whittier - #1400
City/State/Zip: Wichita, KS 67207-1045
Contact Person: Lee E. Phillips III
Phone: 316 681-4470

330 feet from South North line of Section
330 feet from East West line of Section
IS SECTION X REGULAR IRREGULAR?

CONTRACTOR: License # 4958
Name: Mallard JV, Inc.

(NOTE: Locate well on the Section Plat on Reverse Side)
County: NESS
Lease Name: Albers Well #: 1
Field Name: Oppliger
Is this a Prorated/Spaced Field? ... yes X no
Target Formation(s): Mississippian
Nearest lease or unit boundary: 330
Ground Surface Elevation: unknow 2455 feet MSL
Water well within one-quarter mile: ... yes X no
Public water supply well within one mile: ... yes X no
Depth to bottom of fresh water: 180
Depth to bottom of usable water: 160
Surface Pipe by Alternate: 1 2
Length of Surface Pipe Planned to be set: 300 ft.
Length of Conductor pipe required: None
Projected Total Depth: 4600
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
... well ... farm pond X other

Well Drilled For: Well Class: Type Equipment:
Oil ... Enh Rec X Infield X Mud Rotary
Gas ... Storage ... Pool Ext. ... Air Rotary
OWWO ... Disposal ... Wildcat ... Cable
Seismic; ... # of Holes ... Other
Other
OWWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? ... yes X no
If yes, true vertical depth:
Bottom Hole Location:
Exp. 11/17/96

Will Cores Be Taken? ... yes X no
If yes, proposed zone:
300' Alt. II Req.

AFFIDAVIT

RECEIVED

I, the undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et seq.
It is agreed that the following minimum requirements will be met:

MAY 17 1996

Drusher Caral INIT. 302

SPUD DATE 5/24/96 LENGTH SURFACE PLANNED 300 + 312

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

CATHODED AHEAD? Y N SIZE HOLE CONDUCTOR
SURFACE PIPE @ B ELEVATION FORMATION MA-SP

PIPE @ DV TOOL SX ALT II DONE Y N

Arbuckle Plug @ FT. W/ SX

Plug./Council @ FT. W/ SX

Anhydrite Base @ 1776 FT. W/ SD SX

1/2 Base Anyh. @ 888 FT. W/ 80 SX

1/2, 100 Plug @ FT. W/ SX

Bottom Plug @ 333 FT. W/ SD SX

40' Plug @ 40 FT. W/ 10 SX

WATER WELL SX (Irr. Well) Pond ---
Hauling ---

TECHNICIAN DATE

TYPE OF CEMENT DATE

TARTING TIME DATE

COMPLETION TIME DATE

EMENT COMPANY DATE