

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- OWWO  
C NW SE, SEC. 17, T 17 S, R 23 W/4  
1980 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # \_\_\_\_\_  
Operator: State Corporation Commission  
Name & Address \_\_\_\_\_  
\_\_\_\_\_

Lease Name Snodgrass Well # 4  
County Ness  
Well Total Depth 4500 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 458

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor State Corporation Commission License Number \_\_\_\_\_  
Address \_\_\_\_\_

Company to plug at: Hour: 11:30 am Day: 28 Month: July Year: 19 86

Plugging proposal received from \_\_\_\_\_  
(company name) \_\_\_\_\_ (phone) \_\_\_\_\_

were: 4 1/2" at N/A PBDT at 4167' Perfs at N/A Anhydrite 1800' est.

1st plug spotted through tubing 100 lbs. hulls, 20 sx cement, at 4150'

2nd plug spotted through tubing 30 sx cement at 1800'

3rd plug pulled tubing and circulated with 80 sx cement after perforating at 900'

4th plug shut in 8 5/8" casing and pumped 120' sx cement down 4 1/2" casing, the cement dropped to 700' in 4 1/2" and was topped off with 3 yards of ready mix.  
Plugging Proposal Received by Dan Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:30 pm Day: 28 Month: July Year: 19 86

ACTUAL PLUGGING REPORT 1st plug 100 lbs. hulls, 20 sx cement through tubing at 4150',

2nd plug at 1800' with 30 sx cement spotted through tubing, 3rd plug pulled tubing and circulated with 80 sx cement, 4th plug pumped 120 sx cement down 4 1/2" casing -- the cement dropped to 700' in the 4 1/2", topped of with 3 yards of ready mix.

Remarks: Used 60/40 Poz with 6% gel pumped by Allied.  
(If additional description is necessary, use BACK of this form.)

I (did / ~~do not~~) observe this plugging.

AUG 11 1986  
8-11-86

Signed Dan Goodrow  
(TECHNICIAN)