

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24169-00-00  
Spot: SWSWSEW Sec/Twnshp/Rge: 18-17S-23W  
2370 feet from N Section Line, 1525 feet from W Section Line  
Lease/Unit Name: DELANEY Well Number: 1  
County: NESS Total Vertical Depth: 4522 feet

Operator License No.: 6569  
Op Name: SCHMITT, CARMEN, INC.  
Address: PO BOX 47  
GREAT BEND, KS 67530

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 219  
Production: Size feet:  
Liner: Size feet:

\$146.97

Well Type: DH UIC Docket No: Date/Time to Plug: 12/22/2001 12:00 AM  
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC  
Proposal Rcvd. from: BURT Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3141

Proposed Plugging Method: 1ST PLUG AT 1772' WITH 50 SX CMT. 2ND PLUG AT 980' WITH 50 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE  
Date/Time Plugging Completed: 12/22/2001 3:30 AM

WitnessType: Plugging Operations Were Not Witnessed  
KCC Agent: KEVIN STRUBE

Actual Plugging Report:

1ST PLUG AT 1772' WITH 50 SX CMT. 2ND PLUG AT 980' WITH 50 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED  
KANSAS CORPORATION COMMISSION

Signed

Kevin D Strube

(TECHNICIAN)

1-9-02  
JAN 09 2002

INVOICE DEC 28 2001

Form CP-2/3

CONSERVATION DIVISION

Jan 11, 02  
2002061236



# Shields


## WELL LOG

15-135-24169-0000

Russell, Kansas

Operator: Carmen Schmitt, Inc.  
 Well: Delaney #1  
 Commenced: December 12, 2001  
 Completed: December 22, 2001  
 Contractor: Shields Drilling Co.

Well Description: Approx. SW SE NW  
 Sec. 18-17S-23W  
 Ness County, KS



### CASING RECORD

Size	Run	Pulled
8 5/8"	219'	Cmtd. w/150 sax

Elevation: 2,418' KB

Treatment:

Production: D & A

Tops:

RECEIVED

DEC 27 2001

KCC WICHITA

..... Figures Indicate Bottom of Formations .....

Sand, shale, rock	118'	
Shale	222'	
Sand & shale	1,733'	
Anhydrite	1,773'	
Shale	3,683'	
Shale & lime	4,172'	
Lime	4,522'	RTD

Notes