

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21382-00-00
Spot: N2S2NW Sec/Twnshp/Rge: 34-10S-20W
3608 feet from S Section Line, 4003 feet from E Section Line
Lease Name: BRIGGS Well #: 1
County: ROOKS Total Vertical Depth: 3737 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	209		
PROD	4.5	3736		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/01/2012 10:00 AM
Plug Co. License No.: 34115 Plug Co. Name: SCHIPPERS OILFIELD SERVICES, LLC
Proposal Rcvd. from: SCOTT SCHIPPERS Company: SHIPPERS OILFIELD SERVICES, LL Phone: (785) 675-8974

Proposed Plugging Method: Ordered 225 sx 60/40 pozmix 4% gel cement w/200 # hulls

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/01/2012 11:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Rods parted @1025'.
Tubing parted @ 810'.
Went in with washover pipe, couldn't get past 760'. Went in with tubing and bit and got to 812'.
Not making in progress.
Went back in with washover pipe. Could not drill down with mill.
Went in with a "munch" bit. Drilled to 940' and got very hard. Decided to plug there.
Perforated @ 260'.
Ran tubing to 900'. Pumped 180 sx 60/40 pozmix 4% gel to circulate cement to surface. Also circulated 8 5/8"x 4 1/2" annulus to surface.
Pulled tubing. Hooked to 4 1/2" casing. Pumped 30 sx 60/40 pozmix 4% gel. Max pressure of 350 psi.

Remarks: SOS TICKET # 569 Control No. 2012 0034-001

Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN) CM

RECEIVED

MAY 29 2012

Form CP-2/3

MAY 03 2012

KCC WICHITA