

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21359-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 23-13S-20W
1025 feet from S Section Line, 2303 feet from E Section Line
Lease Name: YOUNGER Well #: 1
County: ELLIS Total Vertical Depth: 3832 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217		150 sx
PROD	5.5	3818		150 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/02/2012 11:00 AM
Plug Co. License No.: 34272 Plug Co. Name: OUTLAW WELL SERVICE LLC
Proposal Rcvd. from: JOE BERENS Company: OUTLAW WELL SERVICE LLC Phone: (785) 650-2399

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Arbuckle perms @3818'-3832'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/02/2012 4:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:


Ran in hole with sandline. Stopped @ 1060'.
Ran in hole with bit and tubing to 2013'. No junk or bridges. Decided to plug. Pulled tubing and bit.
Log tech perforated 2 shot holes @ 2200', 1520', 770' and 200'.
Ran in hole with tubing to 2300'. S.O.S. rigged to tubing. Mixed and pumped 115 sx cement with 200 # hulls.
Pulled tubing to 1142'. S.O.S. rigged to tubing. Mixed and pumped 170 sx cement with 400 # hulls to circulate cement up 5 1/2" casing.
Pulled tubing. Topped off 5 1/2" casing with 15 sx cement. Hole standing full.
8 5/8" casing full of cement.

Remarks: S.O.S TICKET # 570 CN: 20100086-001

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

RECEIVED
MAY 23 2012
KCC WICHITA

MAY 03 2012