

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-23904-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 12-24S-4E  
2310 feet from S Section Line, 410 feet from W Section Line  
Lease Name: SOMMERS B Well #: 1  
County: BUTLER Total Vertical Depth: 2528 feet

Operator License No.: 5120  
Op Name: RANGE OIL COMPANY, INC.  
Address: 125 N MARKET ST STE 1120  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	222		180 SX
PROD	4.5	2522		150 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/07/2012 8:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: SAND @ 2440' AND CAP WITH 10 SXS. SHOOT CASING AT 280' AND CIRCULATE TO SURFACE.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/23/2012 11:30 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

4/20/2012 - SANDED OFF TO 2397' AND CAPPED WITH 4 SXS OF 60/40 4% GEL W 3% CALCIUM. SHOT CASING AT 280', RAN TUBING TO 270' AND CIRCULATED, NO RETURN ON CEMENT. PULLED TUBING AND TIED ONTO CASING TO FORCE CEMENT AROUND INTO ANNULUS, STILL NO RETURN. 4/23/2012 - RAN 1" DOWN PRODUCTION STRING AND TAGGED AT 180' AND PUMPED 20 SXS. RAN 1" DOWN BACK SIDE AND TAGGED 6' AND TOPPED OFF. QUALITY WELL SERVICE TICKET #5518.

Perfs:

Top	Bot	Thru	Comments
2464	2470	CSG	

Remarks:

Plugged through: TBG

District: 02

Signed  (TECHNICIAN)  
4/05/12

RECEIVED  
MAY 31 2012  
KCC WICHITA