

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22561-00-00
Spot: NESWSESW Sec/Twnshp/Rge: 4-18S-10W
333 feet from S Section Line, 3626 feet from E Section Line
Lease Name: STUMPS Well #: 4-4
County: RICE Total Vertical Depth: 3346 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3240		
PROD	5.5	3340	1826	150 SX
SURF	8.625	322		185 SX
T1	2.875	3236		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/21/2012 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DIXON Company: D S & W WELL SERVICING, INC. Phone: (620) 786-4258

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DAVID BOLLENBACK Witness Type: NONE
Date/Time Plugging Completed: 05/21/2012 4:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 2970' AND CAP WITH 5 SX'S CEMENT. SHOOT CASING OFF AT 1826' AND PULL TO 1250' AND PUMP 35 SX'S CEMENT WITH 50#'S COTTON HULLS. PULL CASING TO 900' AND PUMP 35 SX'S CEMENT WITH 50#'S COTTON HULLS. PULL CASING TO 372' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3285	3289	CSG	
3276	3280	CSG	
3022	3024	CSG	

Remarks: 60-40 POZ, 4% GEL, QUALITY CEMENT #964. LOG TECH OF KS. #7027. COMPLIANCE TA NOV FROM LEASE INSPECTION.

Plugged through: CSG

District: 02

Signed Virgil Clothier
5/21/12 (TECHNICIAN)

RECEIVED
MAY 31 2012
KCC WICHITA