

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22531-00-00
Spot: SWNENWNW Sec/Twnshp/Rge: 20-18S-9W
340 feet from N Section Line, 740 feet from W Section Line
Lease Name: FREES Well #: 1-20
County: RICE Total Vertical Depth: 3339 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3336	1200	95 SX
SURF	8.625	334		175 SX
T1	2.375	3293		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/16/2012 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DIXON Company: D S & W WELL SERVICING, INC. Phone: (620) 786-4258

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DAVID BOLLENBACK Witness Type: PARTIAL
Date/Time Plugging Completed: 05/16/2012 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS OFF TO 3190' AND CAP WITH 5 SX'S CEMENT. ATTEMPTED TO SHOOT CASING OFF AT 1783' --PERFORATING GUN SHOT OFF AND WIRELINE SNAPPED OFF 30' ABOVE GUN. ATTEMPTED TO SHOOT OFF CASING AT 1274' --WAS UN-SUCCESSFUL. DID GET CASING SHOT OFF AT 1200' AND PUMP 35 SX'S CEMENT WITH 50#'S COTTON HULLS. PULL CASING TO 850' AND PUMP 35 SX'S WITH 50#'S COTTON HULLS. PULL CASING TO 384' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3258	3261	CSG	

Remarks: 60-40 POZ 4% GEL. QUALITY CEMENT TICKET #959. LOG TECH OF KS #7025.

Plugged through: CSG

District: 02

Signed Virgil Clothier
6/15/12 (TECHNICIAN)

RECEIVED

MAY 31 2012

KCC WICHITA

Form CP-2/3

✓