

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00197-00-00
Spot: SW Sec/Twnshp/Rge: 35-21S-33W
1258 feet from S Section Line, 3913 feet from E Section Line
Lease Name: SHOTTENKIRK Well #: 1-35
County: FINNEY Total Vertical Depth: 2710 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: 14950 HEATHROW FORREST PKWY P
HOUSTON, TX 77210

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2550		WITH 5 SX CMT
PROD	5.5	2709	500	WITH 300 SX CMT
SURF	8.625	328		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/10/2012 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: JOEL Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 2550' WITH 5 SX CMT. IF PIPE FREE, PUMP 50 SX CMT AT 2000'. IF INSIDE PIPE PUMP 30 SX CMT AT 2100'. 50 SXC MT AT 1210'. 50 SX CMT AT 370'. 20 SX CMT AT 60'.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: NONE
Date/Time Plugging Completed: 05/10/2012 5:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 2550' WITH 5 SX CMT. PUMP 30 SX CMT AT 2110' THROUGH TBG. RAN BOND LOG. TOC @ 1510'. PERFORATE @ 1150'. SQUEEZE 40 SX CMT AT 1150'. CUT 5 1/2" CASING @ 500'. TOOH W/CSG. RUN TBG TO 388'. CIRCULATE CMT FROM 388' TO 0' WITH 115 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2610	2620		

Remarks: USED CLASS C COMMON BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED
MAY 18 2012
KCC DODGE CITY

RECEIVED
Form CP-2/3
MAY 31 2012
KCC WICHITA