

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-19903-00-00
Spot: NESENWSE Sec/Twnshp/Rge: 1-35S-11E
1970 feet from S Section Line, 1361 feet from E Section Line
Lease Name: CARRIE CRANE Well #: 1
County: CHAUTAUQUA Total Vertical Depth: 1100 feet

Operator License No.: 33874
Op Name: CUSTER OIL & GAS, LLC
Address: JCT HWY 123 & HWY 11 PO BOX 628
BARNSDALL, OK 74002

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/25/2008 10:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' plug at TD, 50' plug at 650' and 350' to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed: 03/25/2008 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1100' and spotted 25 sack plug. Pulled 1" out and pulled on 2" casing. Casing pulled into at 300'. Ran 1" down 8 5/8" casing to 650' and spotted 20 sack plug. Pulled 1" out and perforated casing at 350'. Ran 1" back into 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 155 sacks of cement were used to plug this well. Casing was cut off and location restored.

Perfs:

RECEIVED

KCC Chanute Dist. #3 *DAS*

Remarks: NO CASING INFORMATION ON THIS WELL.

Plugged through: TBG

District: 03

Signed

[Signature]
6/13/12
(TECHNICIAN)

RECEIVED
MAY 31 2012

KCC WICHITA