

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-141-20443-00-00
Spot: SWSESESE Sec/Twnshp/Rge: 26-10S-15W
110 feet from S Section Line, 365 feet from E Section Line
Lease Name: KOELLING - ANGEL Well #: 1
County: OSBORNE Total Vertical Depth: 3400 feet

Operator License No.: 3956
Op Name: BRUNGARDT OIL AND LEASING INC.
Address: 529 E 14TH PO BOX 871
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	219		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/11/2012 12:00 AM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC.
Proposal Rcvd. from: TOM Company: SHIELDS OIL PRODUCERS INC. Phone: _____

Proposed Plugging Method: Ordered 225 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS Witness Type: NONE
Date/Time Plugging Completed: 06/11/2012 11:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

1st plug @990 w/25 sx
2nd plug @565 w/80 sx
3rd plug @269 w/40 sx
4th plug @40 w/10 sx


Rathole 30 sx Mousehole 15 sx

Remarks: QUALITY OIL WELL CEMENT

Plugged through: DP

District: 04

Signed


(TECHNICIAN)
6/11/12

RECEIVED
JUN 18 2012
KCC WICHITA
CM

JUN 21 2012