

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22160-00-01
Spot: NWSESWNW Sec/Twnshp/Rge: 17-9S-21W
3003 feet from S Section Line, 4351 feet from E Section Line
Lease Name: COOLEY AB Well #: B-17
County: GRAHAM Total Vertical Depth: 3802 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		3490		
PROD	5.5	3796		150 SX
SURF	8.625	254		200 SX
SURF	8.625	261		
T1	2.375	3490		

Well Type: EOR UIC Docket No: E26756.2 Date/Time to Plug: 06/12/2012 10:00 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
CIBP @ 3750'.
Perforate open hole 3796' to 3802'.
DV tool 1799' w/ 375 sx cement.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/12/2012 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3000'. Pumped 100 sx cement w/200 # hulls.
Pulled tubing to 2000'. Pumped 100 sx cement w/200 # hulls.
Pulled tubing to 1000'. Pumped 90 sx. Good circulation.
Pulled tubing out. Topped off casing w/15 sx cement. Stayed full.

Perfs:

Top	Bot	Thru	Comments
3750			
3690	3693		
3540	3548		

Remarks: QUALITY WELL SERVICE TICKET # 5585

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

cc to me 6/19/12
6/21/12

CM

JUN 21 2012

RECEIVED
JUN 18 2012
KCC WICHITA