

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21577-00-01
Spot: E2SENWSE Sec/Twnshp/Rge: 21-21S-15W
1654 feet from S Section Line, 1395 feet from E Section Line
Lease Name: KASSELMAN Well #: 1-21
County: PAWNEE Total Vertical Depth: 3975 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3400		
PROD	4.5	3974	1615	WITH 320 SX CMT
SURF	8.625	937		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/11/2012 3:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 1850' & 4 SX CMT. PLUG AT 960' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 06/11/2012 5:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 1881' & 4 SX CMT WITH DUMP BAILER. 1ST PLUG AT 947' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 345' WITH 50 SX CMT. 3RD PLUG AT 43' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3449	3687		
1944	1987		WINFIELD

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
6/21/12 (TECHNICIAN)

RECEIVED
JUN 18 2012
KCC WICHITA

RECEIVED
JUN 14 2012
KCC DODGE CITY

RWL