

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22592-00-01  
Spot: NENWSWSW Sec/Twnshp/Rge: 11-34S-38W  
1288 feet from S Section Line, 603 feet from W Section Line  
Lease Name: VERNA Well #: 11 #4  
County: STEVENS Total Vertical Depth: 6750 feet

Operator License No.: 5278  
Op Name: EOG RESOURCES, INC.  
Address: 3817 NW EXPRESSWAY STE 500  
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6218		WITH 2 SX CMT
CIBP		6533		WITH 2 SX CMT
CIBP		6604		
DVT		3531		
PROD	4.5	6750	2028	WITH 430 SX CMT
SURF	8.625	1696		WITH 480 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/06/2012 2:30 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 6215' WITH 2 SX CMT. PLUG AT 3560' WITH 25 SX CMT. SHOOT CASING @ PUMP 50 SX CMT AT 1730'. PLUG AT 640' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/06/2012 4:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 6533' WITH 2 SX CMT. SET ANOTHER CIBP @ 6218' WITH 2 SX CMT. 1ST PLUG AT 3581' WITH 30 SX CMT AFTER CIRCULATING HOLE WITH MUD. 2ND PLUG AT 1740' WITH 120 SX CMT. 3RD PLUG AT 640' WITH 60 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6608	6613		
6597	6600		
6583	6613		
6268	6288		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

RECEIVED  
JUN 18 2012

KCC WICHITA

District: 01

RECEIVED

JUN 11 2012

KCC DODGE CITY

Signed

*Jack MacLaskey*  
6/21/12  
(TECHNICIAN)