

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22691-00-00
Spot: NWNESWNE Sec/Twnshp/Rge: 8-20S-9W
1412 feet from N Section Line, 1900 feet from E Section Line
Lease Name: PROFFITT Well #: 6-8
County: RICE Total Vertical Depth: 3320 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	348		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/15/2012 5:00 PM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: GARY TOLBERT Company: STERLING DRILLING CO. Phone: (620) 672-9508

Proposed Plugging Method: SPOT 35 SX PLUG ON TOP OF ARBUCKLE, THEN SPOT 35 SX PLUG @ 1250' THEN 35 SX PLUG @ 800', THEN 50' BELOW SURFACE CASING SPOT 35 SX PLUG. THEN @ 60' SPOT 25 SX AND CIRC. TO SURFACE, 25 SX IN RAT HOLE AND 20 SX IN MOUSE HOLE.

Plugging Proposal Received By: DAN FOX Witness Type: NONE
Date/Time Plugging Completed: 06/15/2012 2:45 PM KCC Agent: DAN FOX

Actual Plugging Report:

Perfs:

RTD 3320'. SPOT 35 SX @ TOP OF ARBUCKLE OR @ 3221'. THEN SPOT 35 SX PLUG @ 1248' THEN SPOT A 35 SX PLUG @ 801' THEN A 35 SX PLUG @ 403', THEN 25 SX @ 60' AND CIRC. TO SURF. 25 SX IN RAT HOLE, 20 SX IN MOUSE HOLE. 60/40 POS MIX WITH 4% GEL, ALLIED CEMENTING. TICKET #53627. JOB COMPLETE @ 2:45 PM. ON 6/15/2012. GARY TOLBERT @620-672-9508 EXT. 220 CALLED IN PLUG JOB TO KCC FIELD OFFICE ON 6-15-2012.

Remarks: WELL WAS PLUGGED DUE TO DRY HOLE.

Plugged through: TBG

District: 02

Signed Daniel F. Fox
6/21/12 (TECHNICIAN)

RECEIVED
JUN 20 2012
KCC WICHITA

124