

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23769-00-01
Spot: NWNESENW Sec/Twnshp/Rge: 4-19S-25W
3637 feet from S Section Line, 3244 feet from E Section Line
Lease Name: OMAHA HOTEL Well #: 1-4
County: NESS Total Vertical Depth: 4500 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PC		1750		
PROD	4.5	4494	0	WITH 175 SX CMT
SURF	8.625	220		WITH 140 SX CMT

Well Type: EOR UIC Docket No: E30810.1 Date/Time to Plug: 06/13/2012 12:00 PM
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.
Proposal Rcvd. from: SCOTT HAMPEL Company: MCCOY PETROLEUM Phone: (316) 636-2737

Proposed
Plugging
Method:

THROUGH TBG, SPOT 10 SX GEL & 40 SX CMT AT PERFS. PULL TBG TO PORT COLLAR @ 1750 & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/13/2012 6:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CEMENT WAS VISIBLE WHEN THE BULLPLUG WAS TAKEN OFF THE BRADENHEAD. AT 4338' SPOTTED 10 SX GEL & 40 SX CMT WITH 150# HULLS. PULLED TBG TO 1771' & CIRCULATED CMT TO SURFACE WITH 140 SX CMT. PULLED TBG & TOPPED OFF WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4362	4365		

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

RECEIVED
JUN 21 2012

District: 01

Signed Eric McLaren
(TECHNICIAN)

KCC WICHITA

RECEIVED
JUN 15 2012
KCC DODGE CITY

wa to MC 6/22/12
6/20/12

0000 ✓