

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20915-00-00
Spot: S2NENENE Sec/Twnshp/Rge: 4-33S-19W
441 feet from N Section Line, 318 feet from E Section Line
Lease Name: HERD Well #: 1
County: COMANCHE Total Vertical Depth: 6236 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4930 | | WITH 2 SX CMT |
| COND | 20 | 45 | | WITH 6 SX CMT |
| PROD | 4.5 | 5396 | 1365 | WITH 250 SX CMT |
| SURF | 8.625 | 679 | | WITH 225 SX CMT |

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 06/05/2012 10:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: DAVID HAYES Company: OIL PRODUCERS Phone: (316) 682-3022

Proposed Plugging Method: SET CIBP @ 4935' WITH 2 SX CMT. PLUG AT 950' WITH 15 SX GEL & 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/05/2012 11:45 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4930' WITH 2 SX CMT. 1ST PLUG AT 948' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 705' WITH 50 SX CMT. 3RD PLUG AT 58' WITH 20 SX CMT. CMT CIRCULATED BUT FELL. 6/11/12: TOPPED OFF WITH 3/4 YARD OF READY-MIX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 5116 | 5278 | | |
| 5012 | 5020 | | |
| 4986 | 4994 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED
JUN 21 2012
KCC WICHITA

District: 01

RECEIVED
JUN 18 2012
KCC DODGE CITY

Signed Eric MacLaren
6/18/12 (TECHNICIAN)

AWY