

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00306-00-00
Spot: NENESW Sec/Twnshp/Rge: 4-22S-34W
2500 feet from S Section Line, 2785 feet from E Section Line
Lease Name: WELDON Well #: 1
County: FINNEY Total Vertical Depth: 2626 feet

Operator License No.: 34080
Op Name: GEO. R. SHAW LIVING TRUST
Address: 150 N MAIN, STE 1001
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1085		
PROD	5.5	2625	0	WITH 200 SX CMT
SURF	8.625	302		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/08/2012 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RON OSTERBUHR Company: GEORGE SHAW Phone: (620) 275-7888

Proposed Plugging Method: CIBP W/2 SX CMT OR 20 SX PLUG ON TOP OF FISH. CIBP @ 1100'. TEST CASING TO 700#. PUMP 80 SX CMT + CASING VOLUME. 100 SX CMT DOWN ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/21/2012 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

GLORIETTA CASING LEAK. FLUID LEVEL 500' FROM SURFACE. TBG SANDED IN WTH GLORIETTA SAND. 5/8/12: CUT TBG @ 2284'. COULD NOT PULL. RAN FREE POINT. TBG STUCK @ 1515'. TBG FREE ABOVE THAT. SHOOT TBG OFF AT 1505'. SET CIBP @ 1085'. LOAD & TEST CASING TO 500#. HOLDING. PERFORATE AT 1050'. INJECTION RATE DOWN CASING 1 1/2 BPM @ 450#. 5/21/12: TAKE INJECTION RATE 1 BPM @ 500# DOWN 5 1/2" CASING. NO BLOW OR CIRCULATION UP ANNULUS. PUMP 80 SX CMT, 150# HULLS & 102 SX CMT. PRESSURE INCREASE 100# TO 500# W/HULLS ON PERFS. NO BLOW OR CIRCULATION UP ANNULUS. HOLDING 500#. PUMP 50 SX CMT DOWN ANNULUS & PRESSURE TO 300#. HOLDING. REPRESSURE 5 1/2" CASING TO 700#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2592	2616		
2534	2564		
2510	2525		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

RECEIVED
JUN 21 2012
KCC WICHITA

District: 01

Signed

Ken Jehlik
6/21/12

(TECHNICIAN)

RECEIVED

JUN 07 2012

KCC DODGE CITY

mary