

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20825-00-00
Spot: SESE Sec/Twnshp/Rge: 32-19S-33W
623 feet from S Section Line, 630 feet from E Section Line
Lease Name: BONTRAGER Well #: 1-32
County: SCOTT Total Vertical Depth: 4780 feet

Operator License No.: 31819
Op Name: CHOLLA PRODUCTION, LLC
Address: 7851 S ELATI ST STE 201
LITTLETON, CO 80120

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4304		WITH 5 SX CMT
CIBP		4506		
PROD	4.5	4765	1220	170 SX
SURF	8.625	262		175 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/30/2012 9:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: GILBRALTO Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 4500'. CIBP @ 4300' WITH 5 SX CMT. PULL STRETCH. IF PIPE NOT FREE @ 2240'. PERFORATE 4 HOLES & SQUEEZE 50 SX CMT. IF CAN'T PULL PIPE @ 1250'. PERFORATE 4 HOLES & SQUEEZE WITH 80 SX CMT. PULL CASING. FILL 290' TO 0' WITH CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/30/2012 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4506'. CIBP @ 4304' WITH 5 SX CMT. SHOOT SPLIT SHOT @ 2223' & ATTEMPT TO PULL CASING. COULD NOT WITH 100000#. ESTABLISH INJECTION RATE INTO SPLIT CASING @ 2 BPM @ 1500# BREAKING BACK TO 800#. PUMP 50 SX CLASS C CMT WITH 50# HULLS IN LAST 25 SX. DISPLACE CMT OUT SPLIT TO 2000' @ 800#. HOLDING. RAN SPLIT SHOT TO 1220' & CASING CAME FREE. TOOH W/CASING. RUN TBG TO 1220' & SPOT 80 SX CMT. PULL TO 290' & CIRCULATE HOLE FULL OF CMT WITH 120 SX CMT. STAYED FULL

Perfs:

Top	Bot	Thru	Comments
4682	4686		
4652	4657		
4550	4560		
4454	4458		
4431	4434		
4350	4354		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

RECEIVED
JUN 21 2012
KCC WICHITA

Signed Ken Jehlik
6/20/12 (TECHNICIAN)

District: 01

RECEIVED
JUN 07 2012
KCC DODGE CITY

Handwritten initials