

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-21300-00-01  
Spot: SENWNWSW Sec/Twnshp/Rge: 8-31S-34W  
2000 feet from S Section Line, 4734 feet from E Section Line  
Lease Name: MLP YOUNG A Well #: 1D  
County: SEWARD Total Vertical Depth: 5880 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3550		WITH 2 SX CMT
CIBP		5010		
COND 20		77		WITH 225 SX CMT
DVT		3168		
PROD 5.5		5829	0	WITH 900 SX CMT
SURF 8.625		1681		WITH 645 SX CMT

Well Type: SWD UIC Docket No: D27362.0 Date/Time to Plug: 06/14/2012 2:00 PM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP @ 3550' & 2 SX CMT. PLUG AT 1700' WITH 30 SX CMT. PLUG AT 550' WITH 30 SX CMT. PLUG AT 60' & FILL UP. CHECK BACKSIDE WITH CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/14/2012 5:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5010'. CIBP @ 3550' WITH 2 SX CMT. 1ST PLUG AT 1710' WITH 30 SX CMT. 2ND PLUG AT 550' WITH 30 SX CMT. 3RD PLUG AT 60' WITH 7 SX CMT. PUMP 23 SX CMT DOWN THE ANNULUS TO 500#.

Perfs:

Top	Bot	Thru	Comments
3890	4850		

Remarks: \*\*COMPLIANCE ISSUE: FAILED MIT\*\* USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: TBG

RECEIVED  
JUN 21 2012

KCC WICHITA

District: 01

RECEIVED  
JUN 15 2012  
KCC DODGE CITY

Signed

*Ken Jehlik*

(TECHNICIAN)

cc to MC 6/22/12  
6/24/12

pat