

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-21283-00-00  
Spot: NESENWNW Sec/Twnshp/Rge: 23-27S-15W  
681 feet from N Section Line, 1299 feet from W Section Line  
Lease Name: VERNING EST Well #: 2-23  
County: PRATT Total Vertical Depth: 4641 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4615	819	WITH 150 SX CMT
SURF	8.625	337		WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/05/2012 9:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 50' ABOVE PERFS & PUT 4 SX CMT ON TOP OF SAND BRIDGE. PLUG AT 990' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/06/2012 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4376' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. PICKED UP ON CASING. CASING PARTED SHALLOW. SET CASING BACK DOWN. RUN TBG IN TO 982'. RIG UP PERFORATORS. RUN THROUGH TBG & PERFORATED 4 1/2" CASING @ 990'-991' W/4 HOLES. 1ST PLUG AT 982' WITH 50 SX CMT. LAID DOWN TBG & PULLED & LAID DOWN CASING. RUN TBG BACK IN TO 362'. 2ND PLUG 362' WITH 50 SX CMT. WELL WENT ON VACUUM. SHUT DOWN. 6/6/12: RUN TBG IN & TAGGED TOP OF CMT AT 322'. SPOT 50 SX CMT. 3RD PLUG AT 60' WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4492	4498		

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED COMMON CEMENT BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed

Stephen J. Pfeifer  
6/20/12  
(TECHNICIAN)

RECEIVED

JUN 12 2012

KCC DODGE CITY

RECEIVED

JUN 21 2012

KCC WICHITA

Form CP-2/3

ROW ✓