

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22587-00-00  
Spot: SWNWSENE Sec/Twnshp/Rge: 9-35S-15W  
1758 feet from N Section Line, 1240 feet from E Section Line  
Lease Name: DAVIS TRUST Well #: 9-7  
County: BARBER Total Vertical Depth: 5200 feet

Operator License No.: 32204  
Op Name: REDLAND RESOURCES, INC.  
Address: 6001 NW 23RD ST  
OKLAHOMA CITY, OK 73127

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4950		WITH 2 SX CMT
CIBP		5060		
PROD	4.5	5193	0	WITH 220 SX CMT
SURF	10.75	240		WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/25/2012 9:00 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: ALAN WATSON Company: REDLAND RESOURCES Phone: (580) 571-7609

Proposed Plugging Method: CIBP @ 4950' & 2 SX CMT. FILL CASING FROM 800' TO SURFACE WITH CMT. CHECK BACKSIDE TO 300#.

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: NONE  
Date/Time Plugging Completed: 06/25/2012 10:00 AM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

\*\*CASING LEAKS HAD BEEN SQUEEZED AT 465' TO 496'.\*\* SET CIBP @ 4950' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. RUN CMT BOND LOG FOUND CMT FROM 670' UP TO 100'. RAN OUT OF FLUID. ESTIMATE TOP OF CMT AT SURFACE. RUN TBG INTO 800' & CIRCULATED CMT TO SURFACE WITH 70 SX CMT. LAID TBG DOWN. PUMPED DOWN 4 1/2" X 10 3/4" ANNULUS WITH 12 SX CMT & PRESSURED UP TO 550#.

Perfs:

Top	Bot	Thru	Comments
5076	5118		
5002	5011		

RECEIVED  
JUN 28 2012  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

*Daniel Bernasconi*  
6/25/12 (TECHNICIAN)

RECEIVED  
JUN 25 2012  
KCC DODGE CITY

AMZ