

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20010-00-00
Spot: SWSE Sec/Twnshp/Rge: 2-32S-34W
659 feet from S Section Line, 2045 feet from E Section Line
Lease Name: SILVERMAN Well #: 1
County: SEWARD Total Vertical Depth: 6873 feet

Operator License No.: 34408
Op Name: CISCO OPERATING LLC
Address: 6900 N. DALLAS PKWY, STE 740
PLANO, TX 75024

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4300		
CIBP		5428		WITH 2 SX CMT
PROD	4.5	5663	1694	WITH 125 SX CMT
SURF	8.625	1631		WITH 750 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/11/2012 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 5428' WITH 2 SX CMT. SHOOT CASING & POH. PLUG AT 1665' WITH 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: NONE
Date/Time Plugging Completed: 06/11/2012 10:00 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 5428' WITH 2 SX CMT. SHOT CASING AT 2010' & COULDN'T PULL.
RESHOT @ 1694 & POH W/CASING. 1ST PLUG AT 1694' & PUMPED 80 SX CMT. 2ND
PLUG AT 700' WITH 60 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5478	5542		
4172	4180		

RECEIVED
JUN 28 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE**USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed Jack MacLaskey
7/16/12 (TECHNICIAN)

RECEIVED
JUN 18 2012
KCC DODGE CITY

RMV