

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20967-00-00
Spot: NENESE Sec/Twnshp/Rge: 24-32S-30W
2281 feet from S Section Line, 354 feet from E Section Line
Lease Name: RAMSEY Well #: 2
County: MEADE Total Vertical Depth: 5760 feet

Operator License No.: 33009
Op Name: BIEBERLE OIL & GAS INC.
Address: 405 S MAIN PO BOX 55
MEDICINE LODGE, KS 67104

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5575		WITH 2 SX CMT
PROD	4.5	5760	1986	WITH 130 SX CMT
SURF	8.6285	1630		WITH 480 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/21/2012 2:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 5580' WITH 2 SX CMT. PLUG AT 1660' WITH 15 SX GEL & 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/21/2012 8:15 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

SET CIBP@ 5575' & 2 SX CMT. 1ST PLUG AT 1653' WITH 15 SX GEL & 50 SX CMT.
2ND PLUG AT 620' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Remarks: **COMPLIANCE ISSUE DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL BY ALLIANCE

Plugged through: TBG

District: 01

Signed: Daniel Benson
3/21/12 (TECHNICIAN)

RECEIVED
JUN 22 2012
KCC DODGE CITY

RECEIVED
JUN 28 2012
KCC WICHITA