

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-21388-00-00  
Spot: E2W2NESW Sec/Twnshp/Rge: 12-29S-18W  
1961 feet from S Section Line, 1867 feet from W Section Line  
Lease Name: UNRUH Well #: 1-12  
County: KIOWA Total Vertical Depth: 5000 feet

Operator License No.: 31000  
Op Name: PRATER OIL & GAS OPERATIONS, INC.  
Address: 906 WILLIAM WAY  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4800		WITH 2 SX CMT
PROD	5.5	4996	2200	WITH 100 SX CMT
SURF	8.625	599		WITH 350 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/21/2012 3:30 PM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Revd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (602) 886-5665

Proposed Plugging Method: SET CIBP @ 4800' & 2 SX CMT. PLUG AT 1200' WITH 15 SX GEL & 50 SX CMT. PLUG AT 620' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/21/2012 5:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4800' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 1197' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4864	4884		

RECEIVED  
JUN 28 2012  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed: [Signature]  
(TECHNICIAN)

RECEIVED  
JUN 25 2012  
KCC DODGE CITY

AMY