

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-30207-00-00
Spot: SWNE Sec/Twnshp/Rge: 36-30S-7W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease Name: DURANT Well #: 1
County: KINGMAN Total Vertical Depth: 4718 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4492		
PROD	5.5	4716		175 SX
SURF	8.625	257		200 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/14/2012 4:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2534

Proposed Plugging Method: Per KCC District 2 instructions

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 06/14/2012 4:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 4290' - SET CIBP @ 1500' CAPPED WITH 2 SX CEMENT ON TOP.
CUT CASING OFF @ 1400' PULLED CASING TO 1250' SPOTTED 35 SX CEMENT.
PULLED CASING TO 850' SPOTTED 35 SX CEMENT. PULLED CASING TO 300'
CIRCULATED TO SURFACE WITH 250 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4716	4718		
4332	4339		

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, 60/40 4% POS MIX, TICKET #39697.

Plugged through: CSG

District: 02

Signed

B. J. Hope
7/10/12

(TECHNICIAN) RECEIVED

JUN 29 2012 Form CP-2/3

KCC WICHITA

JK