

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-20361-00-00  
Spot: S2NESESE Sec/Twnshp/Rge: 1-10S-20W  
890 feet from S Section Line, 330 feet from E Section Line  
Lease Name: SUTOR A Well #: 14  
County: ROOKS Total Vertical Depth: 3715 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3713		175 SX
SURF	8.625	249		175 SX
SURF	8.625	250		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/22/2012 8:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Started washover. Tubing and rods @ 1325'.  
3 days of milling and washover. Recovered 125' tubing and rods.  
Unable to get below 1448'. Lost returns, formation cuttings, losing hole  
LKC perms: 3250'-3663'. Was pumping under packer @ 3025'.  
Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/22/2012 10:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to top of fish @ 1448'. Swift Services pumped 160 sx cement. Cement circulated. PTOH. Squeezed w/25 sx cement. Maximum pressure 700 psi. 400 psi shut in. Hooked up to back side and pumped 15 sx. Maximum pressure 250 psi. Shut in pressure 200 psi.

Perfs:

Top	Bot	Thru	Comments
3558	3663		
3446	3450		
3396	3400		
3377	3381		
3250	3254		

Remarks: SWIFT SERVICES

Plugged through: TBG

RECEIVED  
JUL 02 2012

District: 04

Signed Richard Williams  
7/10/12  
(TECHNICIAN)

KCC WICHITA  
CM

JUN 22 2012