

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26323-00-00
Spot: S2NWSNW Sec/Twnshp/Rge: 25-15S-16W
1730 feet from N Section Line, 1650 feet from W Section Line
Lease Name: SANDRA LEAS Well #: 2-25
County: ELLIS Total Vertical Depth: 3520 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13.375	93		90 sx
SURF	8.625	904		370 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/22/2012 12:00 AM
Plug Co. License No.: 5822 Plug Co. Name: VALENERGY, INC.
Proposal Rcvd. from: RANDY MARTIN Company: VAL ENERGY, INC. Phone: (620) 282-1496

Proposed Plugging Method: Ordered 190 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER Witness Type: NONE
Date/Time Plugging Completed: 06/22/2012 9:15 PM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st plug @3400 w/25 sx
2nd plug @950 w/40 sx
3rd plug @300 w/70 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

RECEIVED
JUL 02 2012

KCC WICHITA

District: 04

Signed Ed Schumacher
7/6/12 (TECHNICIAN)

CM

JUN 26 2012