

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21036-00-00
Spot: N2N2SE Sec/Twnshp/Rge: 21-11S-15W
2310 feet from S Section Line, 1320 feet from E Section Line
Lease Name: REICH Well #: 2
County: RUSSELL Total Vertical Depth: 3382 feet

Operator License No.: 7628
Op Name: LORENZEN OIL COMPANY, INC.
Address: 962 BRUSH CREEK MAIN
ARLEY, AL 35541

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3380		150 SX
PROD	4.5	3381		
SURF	8.625	243		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/21/2012 11:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: AVEN WEAVERLING Company: LORENZEN OIL CO. INC. Phone: (785) 623-3221

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Perfs: 1500', 1000', 350' and 233'

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/21/2012 5:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3280'. Pumped 75 sx cement w/100 # hulls.
Pulled tubing to 2100'. Pumped 75 sx cement w/100 # hulls.
Pulled tubing to 1000'. Pumped 50 sx cement.
Cement circulated.
POOH. Hooked on to casing and pumped 20 sx cement @ 600 psi. Shut in.
Hooked to braden head and pumped 500 psi (braden head was full)

Perfs:

Remarks: QUALITY CEMENTING TICKET # 879

Plugged through: TBG

RECEIVED
JUL 02 2012

KCC WICHITA

District: 04

Signed Ray A Dinkel
7/10/12
(TECHNICIAN)

CM

JUN 22 2012