

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25696-00-00
Spot: NESWNENE Sec/Twnshp/Rge: 13-16S-15W
800 feet from N Section Line, 705 feet from E Section Line
Lease Name: BOXBERGER Well #: 1
County: BARTON Total Vertical Depth: 3490 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	434		225 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/12/2012 12:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: JAY Company: SOUTHWIND DRILLING, INC. Phone: (620) 617-4477

Proposed Plugging Method: Ordered 170 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: NONE
Date/Time Plugging Completed: 06/12/2012 3:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

1st plug @3412 w/25 sx
2nd plug @970 w/25 sx
3rd plug @486 w/80 sx
4th plug @40 w/10 sx

Rathole 30 sx

Remarks: QUALITY OIL WELL

Plugged through: DP

RECEIVED
JUL 02 2012
KCC WICHITA

District: 04

Signed Darrel Dipman
7/10/12
(TECHNICIAN)

CM

JUN 19 2012