

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-21668-00-00  
Spot: SESWNW Sec/Twnshp/Rge: 17-13S-21W  
2970 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: KELLER A Well #: 3  
County: TREGO Total Vertical Depth: 4001 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4029		150 SX
SURF	8.625	260		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/21/2012 2:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: MARK ROBBEN Company: MURFIN DRILLING CO., INC. Phone: (785) 735-4621

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/300 # hulls  
DV tool @ 1630' w/410 sx cement.  
Perfs: 3888'-3920'.  
Hole bridged off at 1800' with drill bit stuck in hole. Can not get it out. Shot tubing off at 1780'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/21/2012 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tubing at 1780'. Pumped 125 sx cement. Good circulation.  
Pulled tubing out. Tied onto casing. Squeezed w/40 sx cement. Shut in 400 psi.  
Tied onto back side and squeezed w/5 sx cement. Shut in 350 psi.

Perfs:

Top	Bot	Thru	Comments
3888	3920		

Remarks: ALLIED CEMENT TICKET # 56435

Plugged through: TBG

District: 04

Signed:   
9/10/12 (TECHNICIAN)

RECEIVED  
JUL 02 2012  
KCC WICHITA

CM

JUN 22 2012