

21 R

1

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-20,560-00-00  
C NE SE, SEC. 10, T 19 S, R 25 W/8  
1980 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568  
Operator: Kaiser-Francis Oil Company  
Name & Address P.O. Box 21468, Tulsa, OK 74121

Lease Name Schroyer Well # 1  
County Ness 144.92  
Well Total Depth 4459 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 363

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 7 Month: 10 Year: 19 86

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-659-3165

were: 5 1/2" at 4453' Perfs 4202-02 Anhydrite 1083-1117'

1st plug sand back to 4150' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, 150 sx cement

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:10 p.m. Day: 7 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4150' and dumped 5 sx cement on top of sand through bailer

RECEIVED  
STATE CORPORATION COMMISSION  
CONS. DIV. WICHITA, KS

2nd plug squeezed well with 200 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug, and pumped 150 sx cement.

10-10-1986  
OCT 10 1986

Maximum pressure 750 psi and shut in 400 psi.

Remarks: Recovered 1995' of 5 1/2" casing. Used 60/40 Pozmix 6% gel by B.J. Titan.  
(If additional description is necessary, use BACK of this form.)

UNPLUGGED observe this plugging.

10-12-86

15142  
10-7

Signed Dan Jodice  
(TECHNICIAN)