

238 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,035-00-00
C SW SW, SEC. 2, T 19 S, R 25 (W) X
660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5190
Operator: Sabre Exploration, Inc.
Name & Address: 310 W. Central, Suite 214
Wichita, KS 67202

Lease Name Baldwin Well # 1
County Ness 143.65
Well Total Depth 4420 Mississippi feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 247

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Republic Drilling, Inc. License Number 9943
Address 310 West Central, Suite 214, Wichita, KS 67202

Company to plug at: Hour: 1:30 pm Day: 26 Month: June Year: 19 86

Plugging proposal received from Matt Totten

(company name) Republic Drilling, Inc. (phone) 316-264-0079

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2390
Anhydrite 1690

1st plug at 1650' with 50 sx cement

2nd plug at 800' with 80 sx cement

3rd plug 30' below the base of the surface pipe with 50 sx cement

4th plug from 40' to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement. Plug water Plugging Proposal Received by James R. Kapp well if necessary (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 3:00 pm Day: 26 Month: June Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1690' with 50 sx cement, 2nd plug at 890' with 80

sx cement, 3rd plug at 277' with 50 sx cement, 4th plug from 40' to surface with

10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan
(If additional description is necessary, use BACK of this form.)

INVESTIGATED

RECEIVED
STATE CORPORATION COMMISSION
JUL 7 8 1986
CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lucas (TECHNICIAN)

DATE: JUL 10 1986

INVESTIGATED 2-11 2-1 1986

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 6/16/86 month day year

API Number 15-135-23,035-00-00

OPERATOR: License # 5190 Name Sabra Exploration, Inc. Address 310 W. Central, Suite 214 City/State/Zip Wichita, Kansas 67202 Contact Person Matt Totten Phone (316)-264-2635

C. SW. SW. Sec. 2 Twp. 19 S. Rg. 25 East West 660 Ft. from South Line of Section 4620 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 9943 Name Republic Drilling, Inc. City/State Wichita, Kansas

Nearest lease or unit boundary line 660 feet County Ness Lease Name Baldwin Well # 1 Ground surface elevation 2390 ext. feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Surface pipe by Alternate: 1 2 X Depth to bottom of fresh water 200 Depth to bottom of usable water 800 Surface pipe planned to be set 250 Projected Total Depth 4400 feet Formation Mississippian

Well Drilled For: X Oil SWD Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl Wildcat Cable

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

cementing will be done immediately upon setting production casing.

Date 6/16/86 Signature of Operator or Agent Matt Totten Title President

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 220 feet per Alt. This Authorization Expires 12-13-86 Approved By 5-13-86

Spud 6-16-86 Set 247' 31 ft.

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays). No order have been given - Dan

Table with 3 columns: Plug depth (feet), Plug depth (feet), and Plug depth (feet). Rows include 1st plug @ 1650, 2nd plug @ 800, 3rd plug @ 300, 4th plug @ 40, 5th plug @, and (2) Rathole with 15.

Plug water from bottom to ground level

FUSHER Mat Totten TD 4420 FORMATION Mena SURFACE PIPE 247' @ 8 5/8 ANHYDRITE 1652 ELEVATION NB 2371 STARTING TIME & DATE 6-16-86 COMPLETION TIME & DATE 6-25-86 1st PLUG @ 1650 FT. W/ 50 SX 2nd PLUG @ 800 FT. W/ 80 SX 3rd PLUG @ 300 FT. W/ 50 SX 4th PLUG @ 40 FT. W/ 10 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ Plug water well CEMENT COMPANY BQ TECHNICIAN James Kropp 6-26-86 9:00 AM 60/40 Per 690 gal

07-08-1986 RECEIVED STATE CORPORATION COMMISSION IIII - R 1986 CONSERVATION DIVISION Wichita, Kansas