

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-B5-22432-00-00

SW NW/4 Sec. 19, T 19 S, R 25 W X
660 feet from X/S section line

660 feet from W/X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6278

Lease Name SPRUILL TRUST Well # 1

Operator: PETX PETROLEUM CORP.
Name & Address 1616 GLENARM PLACE
#1700
DENVER, CO 80202

County NESS

Well Total Depth 4630 feet #150.48

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 563'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor BARLOW WELL SERVICE License Number 6690

Address P.O. Box 868, GREAT BEND, KS 67530

Company to plug at: Hour: 9 AM Day: 28 Month: OCT Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO KEITH BARLOW

(company name) BARLOW WELL (phone) _____

were: 4 1/2" @ 4629 - P.B.T.D. @ 4594' - PERFS @ 4552-62' - Plug
off bottom by sanding to 4500' & 4 1/2" Cmt. - RECOVER
2725' - Plug top with 60/40 Pozmix, 2% gel - 3% CC by
Mixing & pumping 3 sz hulls, 15 sz gel, 70 sz Cmt,
10 sz gel, 1 sz hulls, release 8 5/8 plug and follow
w/ 125 sz Cmt.

Signed R. B. Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: _____ Day: 28 Month: OCT Year: 19 83

ACTUAL PLUGGING REPORT Plugged as ordered.

Max. pump pressure @ 1000#
Shut in @ 150#
Cementing by Sun.

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

Signed R. B. Barlow
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
DATE 11-8-83
NOV 2 1983
CONSERVATION DIVISION
Wichita, Kansas
INV. NO. 6026-W