

1052327

TQ:  
STATE CORPORATION COMMISSION

8-7-99

API NUMBER 15-135-24,073 - 60-00  
C SE SW SW SEC. 24, T 19 S, R 25 WCONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINEWICHITA STATE OFFICE BLDG., 130 S. MARKET 4290 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME GANTZ-HOLLOWAY WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY NESSOPERATOR LICENSE # 31242WELL TOTAL DEPTH 4459 <sup>144.92</sup> FEETOPERATOR: SCOUT ENERGY CORPORATION PRODUCTION CSG: SIZE        " FEETNAME AND PO BOX 1348 SURFACE CASING: SIZE 8 5/8" @ 403' WITH        SXADDRESS EDMOND, OK 73083-1348ABANDONED OIL WELL        GAS WELL        INPUT WELL        SWD WELL        D/A XOTHER WELL AS HEREINAFTER INDICATED       PLUGGING CONTRACTOR DISCOVERY DRILLING, INC LICENSE NUMBER 31548ADDRESS PO BOX 763, HAYS, KS 67601COMPANY TO PLUG AT: HOUR: 12:00 PM DAY: 07 MONTH: 08 YEAR: 1999PLUGGING PROPOSAL RECEIVED FROM TOM(COMPANY NAME) DISCOVERY DRILLING, INC (PHONE) 785-623-2920WERE:       1ST PLUG AT 1680' WITH 50 SX CEMENT, 2ND PLUG AT 800' WITH 60 SX CEMENT,3RD PLUG AT 430' WITH 50 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT,5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,6TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT.PLUGGING PROPOSAL RECEIVED BY RICHARD LACEYPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL        PART        NONE XOPERATIONS COMPLETED: HOUR: 2:30 PM DAY: 07 MONTH: 08 YEAR: 1999ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE1ST PLUG AT 1680' WITH 50 SX CEMENT, 2ND PLUG AT 800' WITH 60 SX CEMENT,3RD PLUG AT 430' WITH 50 SX CEMENT, 4TH PLUG AT 40' WITH 10 SX CEMENT,5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT,6TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT.

RECEIVED

STATE CORPORATION COMMISSION

AUG 16 1999

08-16-1999

CONSERVATION DIVISION  
WICHITA, KSREMARKS: USED 60/40 POZMIX 6% GEL 1/2" FLO SEAL BY ALLIED.INVOICES (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)I DID NOT OBSERVE THIS PLUGGING.  
DATE 8-20-99

SIGNED

Richard W. Lacey  
(TECHNICIAN)INV. NO. 60294

FORM CP-2/3