

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 6-14-70 -

C NW NE, SEC. 29, T 19 S, R 25 W Ex  
4620 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Lease Name Schlegel Well # 2

Operator: Kaiser-Francis Oil Co.  
Name & Address: 6733 S. Yale, Box 21468  
Tulsa, OK 74121

County Ness 150.67

Well Total Depth 4636 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 411

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 am Day: 18 Month: September Year: 19 85

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 136-938-2457

were: 5 1/2" at 4624' Open Hole 4623-36'. Perfs at 4516-20'; 4522-24'

1st plug sand back to 4475' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 200 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:30 pm Day: 18 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sand back to 4475' and dump 5 sx cement on top of sand through bailer, 2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls, released 8 5/8" rubber wiper plug and pumped 200 sx cement.

Maximum pressure 400 psi and shut in 200 psi Recovered 1870' 5 1/2" casing.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan (If additional description necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

SEP 27 1985 signed

Signature of Steve Durrant (TECHNICIAN)

CONSERVATION DIVISION Wichita, Kansas

DATE 9-30-85 INV. NO. 10290