

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 5-18-70

NE, SEC. 29, T 19 S, R 25 W/4EX

3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Lease Name Schlegel Well # 1

Operator: Kaiser-Francis Oil Co.
Name &

County Ness 149.50

Address 6733 South Yale
Box 21468

Well Total Depth 4600 feet

Conductor Pipe: Size feet

Tulsa, OK 74121

Surface Casing: Size 8 5/8 feet 411

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:15 pm Day: 18 Month: September Year: 19 85

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4600' Perfs at 4453-56', 4490-93', 4425-28'

1st plug sand back to 4475' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 200 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:20 pm Day: 18 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4475' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls, released 8 5/8" rubber wiper plug and pumped 200 sx cement.

Maximum pressure 500 psi and shut in 400 psi

Remarks: Recovered 1800' 5 1/2" casing. Used 60/40 Pozmix 6% gel by BJ-Titan (If additional description is necessary, use BACK of this form.)

DATE 9-30-85
INV. NO. 10291

RECEIVED
STATE CORPORATION COMMISSION
Signed Dan Jodice (TECHNICIAN)

SEP 27 1985
09-27-1985
CONSERVATION DIVISION