

To: 1 071072  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-23,487-00-00 95P  
150' E & 150' N  
C W/2 NE SEC. 29, T. 19 S, R. 25 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5030  
Operator: Vess Oil Corporation  
Name & Address 8100 E. 22nd St. N, Bldg. 300  
Wichita, KS 67226

4110 feet from S section line  
1830 feet from E section line  
Lease Name Edna Schlegel Well # 1  
County Ness  
Well Total Depth 4607 149.72 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1074

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 16 Month: 6 Year: 19 92

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4599' w/165 sx cement, Open hole 4599-4607'

1st plug sand back to 4550' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 250 sx 60/40 Pozmix 8% gel.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 16 Month: 6 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4550' and dumped 5 sx cement on top of sand through bailer, 2nd plug pumped 300 lbs.

hulls and 250 sx cement down 8 5/8". Maximum pressure 500 psi and shut in 100 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
06-24-1992  
CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 8% gel by Allied. Recovered 3000' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Dan Goodrow  
(TECHNICIAN)

7-8-92  
35643