

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202
12-23
TECHNICIAN'S PLUGGING REPORT

API NUMBER 15- ~~135-20351~~ 135-20409-0000
C NW SE, SEC. 36, T 19 S, R 25 W/8
1980 feet from S section line
1980 feet from E section line

Operator License # 6039
Operator: L.D. Drilling, Inc.
Name
Address: RR 1, Box 183 B
Great Bend, KS 67530

Lease Name Schlegel Well # 1
County Ness 143.85
Well Total Depth 4426 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 608

Abandoned Oil Well Gas Well _____ Input Well _____ SWO Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____
Address _____

Company to plug at: Hour: 10:30 a.m. Day: 23 Month: 12 Year: 19 97

Plugging proposal received from Mike Kasselmann
(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: 5 1/2" at 4415' w/50 sx cement, Open hole, Well has no record of 2nd stage but it has been done
1st plug pump 25 sx cement and 3 sx hulls down 5 1/2" casing,
2nd plug pump 20 sx gel and 140 sx cement down 5 1/2" casing,
Check backside.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 23 Month: 12 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx cement and 3 sx hulls down 5 1/2" casing,
2nd plug pumped 20 sx gel and 140 sx cement down 5 1/2" casing. Maximum pressure 700 psi and
shut in. 500 psi.
3rd plug pumped 15 sx cement down backside. Pressured to 300 psi.

12-24-1997

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.
(If additional description is necessary, use back of this form.)

INVOICED
DATE IAN 06 1998
W/PL 49823
12-23

RECEIVED
Signed _____
(TECHNICIAN)