

15-135-20501-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

APR 1 1975

CONSERVATION DIVISION
Wichita, Kansas

04-01-1975

Operator's Full Name Edmiston Oil Company

Complete Address 801 First Natl. Bank Bldg., Wichita, Kansas

Lease Name Gantz-Holloway Well No. 1

Location SE SE Sec. 13 Twp. 19 Rge. (E) (W) 25

County Ness Total Depth 4399'

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698, Great Bend, Kansas License No. 670

Operation Completed: Hour 1:30 P Day 31 Month 3 Year 1975

The above well was plugged as follows:

Total Depth 4399' 8 5/8 csg set 452' cwc 250 sk.

5 1/2 csg set 4399' cw 100 sk cmt.

Filled 5 1/2 csg W/snd (4399-4390) dumped 5 sk cmt W/dump bailer. (4390-4360)

Cutoff & recovered A/2400' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg with 27 sk gel & water W/100 lbs hulls -released

8 5/8 plug & 100 sk poz (50-50) 6% -displaced with 8 sk gel & water & capped

with 20 sk poz (50-50) 6% by Sun cementing Co. PP 500 lbs. SIP 200 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Red? M...?
Well Plugging Supervisor

4/1/75

1070-W