

15-135-20513-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

FEB 26 1973  
02-26-1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Thunderbird Drilling, Inc.

Complete Address Box 18407 Wichita, Kansas 67218

Lease Name Schlegel Well No. 2

Location C SW NW Sec. 10 Twp. 19 Rge. (E) (W) 25

County Ness Total Depth 4590'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co., Inc.

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 12:45 P Day 24 Month 2 Year 1973

The above well was plugged as follows:

Total Depth 4590' 8 5/8 csg set at 330' cwt 225 sk.

5 1/2 csg set at 4589' cw 225 sk cmt.

Filled 5 1/2 csg W/sd (4575-4590) dumped 5 sk cmt W/dump bailer. (4540-4575)

Cutoff and recovered 2600' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/300 lbs hulls -released 8 5/8 plug

& pumped 100 sk cmt -displaced with 8 sk gel & water & capped with 20 sk cmt.

PP 500# SIP 150 lbs. by Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: Bio Z Messer  
Well Plugging Supervisor

RECORDED

2/28/73

9050-W