

15-135-20505-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
06-19-1972
JUN 19 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thunderbird Drilling, Inc.
Complete Address P. O. Box 18407 Wichita, Kansas 67218
Lease Name Standish Well No. 1
Location SW SE Sec. 8 Twp. 19 Rge. (E) (W) 25
County Ness Total Depth 4561'
Abandoned Oil Well XI Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling Co., Inc.
Address Box 405 Chase, Kansas 67524 License No. 436
Operation Completed: Hour 12:30P Day 16 Month 6 Year 1972

The above well was plugged as follows:

Total Depth 4561' 8 5/8 csg set at 330' cwc: Cmt. Mat. 50-50 poz cmt W/6% total gel.

5 1/2 csg set at 4552' cw 125 sk cmt.

5 1/2 csg PBTD 4460' with top perf. (4342')

Filled 5 1/2 csg W/sd (4325-4460) Dumped 5 sk cmt W/dump bailer. (4290-4325)

Cutoff and recovered 2700' of 5 1/2 csg.

Pumped down 8 5/8 csg with 24 sk gel W/250 lbs hulls, released plug and pumped

100 sk cmt, 6 sk gel & water, 20 sk cmt W/50 lbs hulls. by Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo P. Murray
Well Plugging Supervisor

INVOICED

DATE: 6/20/72
5905-W