

15-135-20538-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION

AUG 7 1972

CONSERVATION DIVISION  
Wichita, Kansas

08-07-1972

Operator's Full Name Thunderbird Drilling, Inc.  
Complete Address Box 18407 Wichita, Kansas 67218  
Lease Name Spruill "B" Well No. 1  
Location SE SE SW Sec. 33 Twp. 19 Rge. (E) (W) 25  
County Ness Total Depth 4500'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 3 P Day 2 Month 8 Year 1972

The above well was plugged as follows:

Total Depth 4500' 8 5/8 csg set at 400' cwo Cmt. Mat. 50-50 poz cmt W/6% total gel.

5 1/2 csg set at 4496' cw 100 sk cmt.

5 1/2 csg PBD 4482' with perf. (4424-4428)

Filled 5 1/2 csg W/sd (4400-4482) Dumped 5 sk cmt W/dump bailer. (4365-4400)

Cutoff and recovered 3620' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released 8 5/8 plug, -

pumped 85 sk cmt, -8 sk gel & water & 15 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 8-7-72

INV. NO. 6126-10